JOHNSTOWN

Johnstown Corporation Johnstown, Pennsylvania

SMART PUMP Case Study

Prepared by:

MT Systems, Inc. 110 E. Williams Street Danville, IL 61832 Phone: (217) 446-4646

April 1993

Copyright © 2000 M T Systems, Inc.

JOHNSTOWN

SMART PUMP

Introduction

Johnstown Corporation (Formerly USX) has been in operation for 99 years. They specialize in medium to large steel castings and rolling mill rolls. Production capacity at this facility is roughly 25,000 tons per year utilizing Alkyd Oil, Phenolic Urethane No-Bake and Clay Bonded core and mold technologies.

General Foundry Information	
Product Line:	Steel castings for automotive, industrial, naval, and power generation
	Steel and iron rolls
Casting Metal Type:	Steel 90% of Production
	Iron Rolls 10% of Production
Melting Facilities:	(1) 30 Ton Electric Arc Furnace
	(2) 8 Ton Electric Arc Furnaces
	(2) 4 Ton Induction Furnaces
	(1) 25 Ton Ladle Station
Sand Facilities:	Core Processes Phenolic Urethane Alkyd Oil
	Molding Processes Phenolic Urethane Alkyd Oil Clay Bonded Silica
Cleaning Facilities:	Hand RotoBlast (2)
	Cleaning Booths
	Grinding
	Riser Burn Stations (1)
Heat Treating:	• Ovens (12)
	Quench and Temper
	Stress Relieve
	Normalize
Pattern Shop:	Wood, Styrofoam, Urethane Patterns

JOHNSTOWN

SMART PUMP

Project Objective

The objective of the project was to reduce binder consumption and improve process repeatability. Additionally, high / low binder recipe capabilities and reduced mechanical problems were needed.

Original Problems

- Continuous maintenance problems with existing chemical addition system
- Inaccurate and inconsistent chemical additions
- Addition of extra chemical to compensate for pumping fluctuations
- Resin and labor costs associated with daily calibrations of pumping system
- Scrap molds due to fluctuations in chemical delivery

Solution

They installed the MT Systems SMART PUMP Control System on three of their continuous mixers. This was done in three stages with a design to give them the consistent repeatable chemical addition along with greatly improved mechanical reliability.

To accomplish this, each mixer was outfitted with the following hardware:

- SMART PUMP panel containing flowmeters, motor controllers, motors, magnetically coupled pumps, diverter valves and controllers
- Mixer controls were altered to accommodate the SMART PUMP systems
- Alarm lights and horns were mounted near the mixer

The system fully compensates for line restrictions, chemical viscosity changes, pump wear, and operating pressure changes. If for any reason the chemical levels can not reach their set point and SMART PUMP is unable to compensate, the system alarms to notify the operator or shuts down.

MT Systems Case Study of:

Page 4 of 4

JOHNSTOWN

SMART PUMP

Results and Benefits

- Reduced average chemical levels by 15%
- Reduced maintenance downtime and maintenance expenditures
- Reduced mold scrap by 80%
- Increased productivity by making the job right the first time
- Better shake out due to reduced resin levels

Monetary Savings/Pay Back

The original projected time was 14 months and the actual pay back was 9 months.